

Chalk/pencil line inside
dimension for Rafter and
Ridge Beams.

H
D



Install cleating for Rafter and Ridge Beam



Install cabling to structural blocking in ceiling. Cut holes in bottom of Ridge Beam and install ridge beam.



Install Rafter Beams.





Install LVL hanger to structural blocking in wall. Install LVL and turnbuckle kit. Cabling requires 2 wire clamps to each side of yoke.

At this point add 2X blocking to LVL every 24" on center for Bottom Chord install.





Install Bottom Chord and it's fourth side.

Install King Post and it's fourth side.



Install Webbing and the fourth side to each.

